

Swimming Pool/Hot Tub Install Guidelines



*****A Plat of Survey is required when applying for a preliminary pool inspection*****

* A Preliminary pool inspection is required before a pool is installed. This inspection is to make sure that the property meets all of the requirements to install a pool. **If the preliminary inspection is approved then a permit can be issued to install a pool.**

* If a contractor is installing the pool, that contractor must be licensed and bonded with the Village of Stickney.

* Pool must be at least 3ft off each lot line and at least 3ft away from any structure or building, with the exception of an attached permanent deck or patio.

* The property is required to have a latched fence on all sides.

* Above ground pools cannot exceed 6ft in height, including attached fences, railing, lattice, and/or structural and decorative additions.

* In-ground pools will require additional fencing around the pool or deck area.

* **Extension cords are not allowed to be run to the pool.**

* All electrical supply requirements must be installed by a licensed electrical contractor. See page 2 for swimming pool and hot tub electrical tie-in requirements.

* Pool permits will cost a minimum of \$125 - this includes the preliminary inspection, a final building inspection, a \$50 permit fee, and a \$75 final electrical inspection.

* Before making purchase it is good practice to ensure it can meet all village requirements.

Village of Stickney Building Department

Email: building@villageofstickney.com

6533 Pershing Rd.

Ph: 708-749-4400

Village of Stickney

Swimming Pool Electrical Tie-In

* Electrical, no overhead utility electric wires or conductors shall cross any part of the pool area or be located within 10 feet of either side of the pool line measured horizontally.

* Underground service cable shall not be permitted under the pool or within 5 feet of the inside wall of the pool. When space limitations prevent service cable from being routed 5 feet from the pool, such cables must be installed 24" deep in 4" conduit at customer's expense.

Requirements

1. Size of underground conductor - 12GA minimum.
2. Ridgid conduit 1/2" minimum.
3. A dedicated GFCI protected circuit is required.
4. Outlet should be no closer than 6 feet from pool.

Hot Tub Electrical Tie-In

* Horizontal limit of aerial clearance will not measure less than 10 feet from the inside wall of the hot tub.

* Underground service cable shall not be permitted under the hot tub or within 5 feet from the inside wall of the hot tub. When space limitations prevent service cable from being routed 5 feet from the pool, such cables must be installed 24" deep in 4" conduit at customer's expense.

***** All Electrical work must be completed by a licensed electrical contractor in the Village of Stickney.*****

Village of Stickney Building Department
Email: building@villageofstickney.com

6533 Pershing Rd.
Ph: 708-749-4400